(19)

CITY OF WILLIAMSPORT, PA
RESOLUTION

RESOLUTION # 9860 **DATE** 11-7-24

TITLE

RESOLUTION AUTHORIZING AN AGREEMENT BETWEEN THE WILLIAMSPORT BUREAU OF FIRE AND TRUE GRADE EXCAVATING & HAULING

NOW, THEREFORE BE IT RESOLVED that the City Council of the City of Williamsport authorizes the Williamsport Bureau of Fire to enter into an agreement with True Grade Excavating & Hauling, 2496 Jacks Hollow Road, Williamsport, PA 17702 for conduit to be run from the firehouse to the new shed for electrical and gas line services, price not to exceed $4,215.36. This will be funded by the PA Municipal Fire Department Capital Grant.

HEREBY, the appropriate City Officials are hereby authorized to execute an agreement between the Williamsport Bureau of Fire and True Grade Excavating & Hauling, and to sign such documents necessary to carry out the intent of this Resolution.

Approved

Joanne M. Frank
City Clerk

President

Approved

Derek Slaughter — 11/8/24

Mayor, Derek Slaughter — Date

Janice M. Frank — 11-7-24

City Clerk, Janice Frank — Date

Peg Woodring — 11-7-24

Controller, Peg Woodring — Date

Quote

TRUE GRADE
Excavating & Hauling

True Grade Excavating LLC.
2496 Jacks Hollow Rd
Williamsport, Pa 17702
570-916-0322

Customer Info: Williamsport Bureau of Fire
440 Walnut Street
Williamsport, Pa 17701
Attn: Chief Aungst

Electric Service Trench

Itemized Costs		Amount
-Dig a trench from the firehouse to the new shed. 77'x2.5'x2' -Install approx: 2" of screenings on the bottom of the trench to bed the conduit. -Install 2" conduit from the firehouse to the new shed. -Install approx: 6" of screenings on top of the conduit. -Install and compact 2A sub-base within 4.5" of grade. -Install and compact binder to grade.		
	Screenings	$130.00
	2A	$189.00
	Conduit	$207.36
	Fittings	$59.00
	Binder	$580.00
	Machine time + labor	$2,000.00
	Trucking	$500.00
	Total:	**$3,665.36**

Terms of Service:

Pricing provided is an estimate and based on the information we have, in the event unforeseen circumstances would result in additional time or materials, True Grade Excavating will provide notice and detail of the additional costs that would result. A 50% down payment is due 1 week prior to the start of the job. Balance is due the day the job is completed.

Customer Acceptance:

Sign _____ Date _____

Quote

TRUE GRADE
Excavating & Hauling

True Grade Excavating LLC.
2496 Jacks Hollow Rd
Williamsport, Pa 17702
570-916-0322

Customer Info: Williamsport Bureau of Fire
440 Walnut Street
Williamsport, Pa 17701
Attn: Chief Aungst

Electric Service Trench

Itemized Costs	Amount
-Dig a trench from the firehouse to the new shed. 77'x2.5'x2' -Install approx: 2" of screenings on the bottom of the trench to bed the conduit. -Install gas service line to the new shed. -Install approx: 6" of screenings on top of the gas line. -Gas line to be installed in the same trench as the electrical conduit.	
Extra cost to install the gas line beside the electrical conduit:	$550.00

Terms of Service:

Pricing provided is an estimate and based on the information we have, in the event unforeseen circumstances would result in additional time or materials, True Grade Excavating will provide notice and detail of the additional costs that would result. A 50% down payment is due 1 week prior to the start of the job. Balance is due the day the job is completed.

Customer Acceptance:

Sign _____ Date _____